TOWNOR	ONTARIO B STANDAF	Building Services Division 32 Mill Street Thornbury, ON N0H 2P0 Tel.:(519) 599-3131, ext. 239 Toll Free: 1-888-258-6867			
E MOUNT	Verification of Fire Alarm Systems		Fax: (519) 599-7723 build@thebluemountains.ca www.thebluemountains.ca		
Date Issued:	Dec. 11, 2014	Standard Practice No.:	SP.OBC.15.19		
Date Effective:	Dec. 11, 2014	OBC Ref.:	3.2.4.5.(1), Div. B		
Date Revised:	Jun 13, 2016	Issued By:	Chief Building Official		

Purpose

The intent of this Standard Practice is to clarify the acceptable criteria for the verification of Fire Alarm Systems and to clarify individuals who should be completing the testing and verification of those systems regulated under the Ontario Building Code.

Background

Ontario Building Code References

3.2.4.5. Installation and Verification of Fire Alarm Systems

(1) Fire alarm systems, including those with voice communication capability, shall be installed in conformance with CAN/ULC-S524, "Installation of Fire Alarm Systems".

(2) A fire alarm system shall be verified in conformance with CAN/ULC-S537, "Verification of Fire Alarm Systems", to ensure satisfactory operation.

CAN/ULC-S537 References

The preface of the CAN/ULC Standard contemplates that the verification procedure described herein will be conducted by an organization other than the installing contractor and designer, and that the verification will be carried out by qualified personnel in the employ of an organization acceptable to the authority having jurisdiction.

Standard Practice

Verification Certificates

CAN/ULC-S537 and all of the NFPA standards that cover fire suppression systems contain requirements for performing testing and/or verification of the systems after installation is complete and before the systems are put into operation.

1. The Building Services Division is the Authority Having Jurisdiction (AHJ) and to confirm that the testing and verification of the fire alarm and/or fire suppression system has been performed according to the relevant standards, the person or company responsible for the verification shall provide documentation to the Chief Building Official in the form set out in Appendix A and B of this Standard Practice.

The documentation provided should contain the following information:

- a. the name of the person or company performing the test or verification,
- b. the name of the building owner or designer/design engineer for whom the test or verification is being done,
- c. the name of the designer,
- d. the name of the contractor who installed the system,
- e. the name of the contractor who updated the drawings and specifications to 'asbuilt' status,
- f. the address of the building where the system is installed,
- g. the date of installation of the system,
- h. the date on which the system was tested or verified,
- i. the codes and standards to which the system was tested or verified, the signature of the person responsible for the verification, and
- j. the professional's seal if required (see items 2 and 3 below).

In addition to the requirements listed above and set out in Appendices A and B, the various NFPA standards and CAN/ULC-S537 contain document templates for reporting on the testing and verification of fire alarm and fire suppression systems.

- 2. For buildings that are required by Article 1.2.2. of Division C to be designed and to have construction reviewed by Architects **and/or** Professional Engineers, the following conditions shall be met:
 - a. the verification of the fire alarm system and the required documentation of that verification must be completed under the direction of a Professional Engineer who, through training and experience, is familiar with the installation and functional requirements of fire alarm systems; and
 - b. once the verification of the fire alarm system is complete, the Certificate of Verification (see Appendix A) is to be sealed by the Professional Engineer assuming responsibility for the verification.
- 3. For buildings that are **not** required by Article 1.2.2. of Division C to be designed and to have construction reviewed by Architects or Professional Engineers, the following conditions shall be met:
 - a. the verification of the fire alarm system and the required documentation of that verification should be completed under the direction of
 - i. the person responsible for the design and/or construction review who, through training and experience, is familiar with the installation and functional requirements of fire alarm systems, or
 - ii. an independent third party who, through training and experience, is familiar with the installation and functional requirements of fire alarm systems; and

b. once the verification of the fire alarm system is complete, the Certificate of Verification (see Appendix A) should be signed by the person assuming responsibility for the verification,

Existing Fire Alarm Systems

When an existing Fire Alarm System (FAS) in a building is subjected to an addition or alteration (replacement of components, addition, modification, repair, adjustment to system hardware, or any change to software), then the extent of the Fire Alarm System re-verification shall be provided as follows:

- 1. When a control unit, CACF or an annunciator has been replaced, repaired or modified on the existing FAS the entire FAS <u>shall be re-verified</u>.
- 2. When a component or components of the existing single zone fire alarm system have been subjected to an addition or modification the entire FAS <u>shall be re-verified</u>.
- 3. When fire alarm initiating devices have been added or modified in a fire alarm initiating zone (a manual station, a smoke detector, a flow switch or a heat detector), then that entire fire alarm initiating zone *shall be re-verified*. (See Notes).
- When audible signal devices have been added or modified in a fire alarm signaling zone (speakers, bells, vibrating gongs, etc.) then that entire fire alarm signaling zone <u>shall be re-verified</u>. (See Notes).
- 5. When an existing fire alarm system component (a field device, voice communication module, a control unit, annunciator, etc.) has been modified or replaced with a component from a different manufacturer, all existing and new/modified devices must be compatible. The requirement of Clause 3.1.4 of the Standard ULC S524 states that "All devices incorporated in a fire alarm system shall be compatible".
 - a. Therefore, such compatibility shall be indicated on the Appendix C form by providing a compatibility test report from the ULC. The referenced test report must accompany each completed Appendix C form submitted in accordance with this Standard Practice.

Notes:

1. Section 6 of ULC S537, "System Modification", provides specific verification requirements for modified fire alarm systems.

Clause 6.2 of ULC S537 offers a clarification for modified "conventional field devices" by indicating that where a conventional filed device is added or modifications are made to an existing input circuit or output circuit and the wiring is extended from an existing field device, the new device(s) as well as the existing device(s) connected on either side of the added or modified device and the end of the line for that circuit shall be verified for correct operation.

For the purpose of items 3 and 4 of this Standard Practice, provision of Clause 6.2. of ULC S537 is deemed to be acceptable to this office, when only *a minor modification* is made to an existing fire alarm initiating or signaling zone (i.e., Page-3 - of 4

replacement, relocation or addition of not more than 10% of conventional field devices in the zone).

2. Conventional filed device is defined by ULC S537 as follows:

"Conventional Field Device – A field device that is usually connected to the control unit on a common wiring circuit with other devices on the circuit provide common status change information (e.g. Fire alarm detection or signaling). Such devices cannot be uniquely identified by the control unit unless there is only one device on the circuit. (Refer to active field devices.)"

References and Related Policies

Ontario Building Code CAN/ULC-S537, ""Verification of Fire Alarm Systems",

Review Cycle

This policy will be reviewed annually by the Chief Building Official.

TOWN OF THE BLUE MOUNTAINS

Greg Miller, BSSO, CBCO, C.E.T. Chief Building Official Tel: (519) 599-3131 ext. 261 Toll Free: 1-888-258-6867 <u>CBO@thebluemountains.ca</u>



CAN/ULC S537-04 (AMENDED FOR CAN/ULC-S524-06) APPENDIX "C" (INFORMATIVE) – FIRE ALARM SYSTEM (FAS)

VERIFICATION REPORTS

(Reference: Subsection 4.1-Note, Clause 4.2.1, 4.2.2)

C1. FIRE ALARM SYSTEM VERIFICATION REPORT

(Reference: Clause 4.1.6, 4.1.7, 4.2.2)

	Electrical Permit Number:	-		l	Date:		
	Building						
	Name &						
	Address: New FAS			Existing FAS 🔲 (See	Note 1)		
	System Manufacturer:			Model Number:			
	· · · · · · · · · · · · · · · · · · ·						
Α	System provides single-stage of	operation.			Yes 🗌	No 🗌	
В	System provides two-stage ope	eration.			Yes 🗌	No 🗌	
2	The entire fire alarm system ha	as been verified in ac	cordance with CAN/ULC	C-S537-04, Standard for	Voc 🗆		
C	Verification of Fire Alarm Syste	ems.					
D	This is a partial verification for a	a partial occupancy.			Yes 🗌	No 🗌	
	Components of the existing Fire	e Alarm System have	e been modified or repla	ced with components fror	ma		
F	different manufacturer and are	compatible with the (existing Fire Alarm Syst	em components (See No		No 🗆	

	2)			
F	This is a partial verification for a <i>Fire Alarm System</i> that has been replaced in stages.	Yes 🗌	No 🗌	
G	This is a verification of a portion of an existing <i>Fire Alarm System</i> verified in accordance with Section 6, <i>System Modifications</i> .	Yes 🗌	No 🗌	
н	Installed in accordance with the design and CAN/ULC-S524, <i>Standard for the Installation of Fire Alarm Systems</i> .	Yes 🗌	No 🗌	
Ι	The <i>Fire Alarm System</i> documentation is on site and includes a description of the system.	Yes 🗌	No 🗌	
J	The Fire Alarm System is now fully functional with 🔲 without 🗌 deficiencies. (See Note 3)	Yes 🗌	No 🗌 N/	A 🗌
к	The <i>Fire Alarm System</i> is connected to an acceptable ULC Listed central monitoring station. The communicator is ULC Listed for the purpose. The connections between the FAS and the communicator are supervised. If connected, the name and location of the central monitoring station is:	Yes	No 🗌 No 🗍 No 🗌	
	ULC "Central Station Fire Protective Signalling Service" Certificate Number: which is issued for the above noted central monitoring station address is is is not is attached.	_		
L	Comments:			

A copy of this report will be given to: who is the owner or owner's representative for this *building*.

CERTIFICATION

Yes 🗌

No 🗌

This certifies that the information contained in this *Fire Alarm System Verification Report* (which incorporates the attached pages) is correct and complete. The system and equipment described here-in was tested/inspected in conformance with CAN/ULC-S537-04 by a qualified technician. The equipment was left in an operational condition except as noted above. A copy of this report must be maintained on the premises for examination by the Fire Marshal, Building Inspector, or other *Authority Having Jurisdiction* at their request.

Supervising Technician:	Company & Contact Information:	
		_
Print Name:		
	Telephone:	
Assisting Technician/Electrician:	Company & Contact Information:	
		(Stamp Field)
Print Name:		
	Telephone:	
Designer:	Company & Contact Information:	
Print Name:		
	Telephone:	

NOTES:

- 1. Extent of Verification of the existing FAS:
- 2. If "Yes", ULC test report/compatibility listing is attached.
- 3. The identified deficiencies relate to:

(a) the existing portion of the FAS not covered by the scope of work under the above referenced permit.

(b) the newly installed FAS (or modified/added portion of FAS) under the above referenced permit.

Date:		Audit	Verification
Building Name:	Address:		

"Yes" - Tested correctly "No" - Did not test correctly (NO answers are typically detailed in "Comments/Remarks") "NA" = Not applicable

		C2. Documentatio	n			
				Yes	No	N/A
Α	Instructions for resetting	the system and silencing alarm	signals.			
В	Instructions for silencing the trouble signal sounds	the trouble signal and action to s.	be taken when			
С	Description of the function fire alarm control unit.	on of each operating control and	indicator on the			
D	Description of the area or circuit (this may be in the	r fire zone protected by each ala form of a list or plan drawing).	arm detection			
Е	Description of alarm sigr	al operation.				
F	Description of ancillary e	quipment controlled by the fire a	alarm system.			
G	In systems that provide I documentation is on site smoke control system. Smoke control installed i	ogical control of a smoke contro and includes a sequence of ope n accordance with Measure:	I system, eration of the			
Н	Building diagrams are or all smoke control equipm	n site that clearly indicate the typ nent (fans, dampers, etc.).	e and location of			
Recom	nended Additional Docu	mentation (not mandated by t	he Standard):	Yes	No	
	Additional documentation building is appended to t	n relating to smoke control meas his report.	sures in the			
	Fire Safety Plan docume	ntation is on site.				
	Instructions to Occupant	s/Evacuation Floor Plans are po	sted.			
			remotely installed amp supervised power sup remote sequential disp	lifiers in plies in t play unit	this FA this FAS s in this	IS. 3. FAS.
	There are a total of:		remote annunciators ir remote trouble units in	this FA	AS. S.	
	_		remote booster/power	supplie	s in this	FAS.
Li	st all locations where re	note booster/power supplies	, batteries & amplifiers	s are in	stalled:	

	C3. Field Device and Related Circuits – Test and Inspection	n		
		Yes	No	N/A
А	Correct field termination and wiring size.			
В	Correct circuit polarities.			
С	An open circuit fault on a conventional device circuit causes a trouble signal.			
D	Removal of any active or supporting field device circuit causes a trouble signal.			
Е	One contact device and one non-contact device tested for operation and annunciation at the control unit or transponder, when using a field verifying device.			
F	Class "A" circuits serving conventional field devices tested for the capability of providing an alarm signal on each side of an open circuit fault connection at the electrically most remote point in the circuit.			
G	Ground fault indications occur when tested at the electrically furthest field device, and do not result in normal to off-normal status change conditions.			
н	Field device at the electrically furthest point from the power source (in every circuit) receives rated power in accordance with the manufacturer's specifications.			
I	Replaceable over-current devices are of the correct rating.			
J	Where a power buss circuit serves more than one fire alarm zone, a single fault (open circuit fault, short circuit fault or ground fault) on the power circuit does not prevent the normal operation of input or output field devices in more than one fire alarm zone.			
к	Conductor type and wire gauge are in accordance with the equipment manufacturer's installation wiring requirements at all system termination points.			
L	Confirm that where multiple strand optical fibre cable used with a fire alarm system is not dedicated to the fire alarm system, the fire alarm system shall continue to function as required despite impairment to other systems which may share the cable.			

Date:		Audit	Verification
Building Name:	Address:		

	C4. Data Communication Link Testing			
Contro	ol Unit/Transponder Field Location:			_
Contr	rol Unit/Transponder Identification:			_
	DCL Identification:	1		
		Yes	No	N/A
A	Each system abnormal condition specified in Table 1 – Abnormal System Conditions, tested for each data communication link at the control unit or transponder.			
В	Tests for alarm and trouble received under a single ground fault condition conducted on each conductor of that data communication link independently.			
С	Each conductor in a data communication link, Class A (DCLA) tested for the capability of providing an alarm signal on each side of a single open circuit fault condition.			
D	Where a data communication link serves devices on more than one floor area, impose a wire-to-wire short circuit fault within each floor area and confirm receipt of trouble and alarm condition from another floor area.			
E	Where fault isolation modules are installed in data communication links serving field devices, wiring shorted on the isolated side, annunciation of the fault confirmed, and then a device on the source side operated, and activation confirmed at the control unit or transponder.			
F	Where fault isolation in data communication links is provided between control units or transponders, the field wiring shorted between each pair of control units or transponders, in turn, annunciation of the fault confirmed and operation outside the shorted section is confirmed.			
Contro	I Unit/Transponder Field Location:			
Contr	rol Unit/Transponder Identification:			-
	DCL Identification:			-
		Yes	No	N/A
A	Each system abnormal condition specified in Table 1 – Abnormal System Conditions, tested for each data communication link at the control unit or transponder			
В	Tests for alarm and trouble received under a single ground fault condition conducted on each conductor of that data communication link independently.			
с	Each conductor in a data communication link, Class A (DCLA) tested for the capability of providing an alarm signal on each side of a single open circuit fault condition.			
D	Where a data communication link serves devices on more than one floor area, impose a wire-to-wire short circuit fault within each floor area and confirm receipt of trouble and alarm condition from another floor area.			
E	Where fault isolation modules are installed in data communication links serving field devices, wiring shorted on the isolated side, annunciation of the fault confirmed, and then a device on the source side operated, and activation confirmed at the control unit or transponder.			
F	Where fault isolation in data communication links is provided between control units or transponders, the field wiring shorted between each pair of control units or transponders, in turn, annunciation of the fault confirmed and operation outside the shorted section is confirmed.			

Date:		Audit	Verification	
Building Name:	Address:			

C5. Control Unit or Transponder Record (Reference Clause 5.1.1)

C5.1 Control Unit or Transponder Tests					
Control Unit/Transponder Field Location:					
Control Unit/Transponder Identification:					
	Yes	No	N/A		
A Power 'on' visual indicator operates.					
B Common visual trouble signal operates.					
C Common audible trouble signal operates.					
D Trouble signal silence switch operates.					
E Main Power supply failure trouble signal operates.					
F Ground fault tested on positive and negative initiates trouble signal.					
G Alert signal operates.					
H Alarm signal operates.					
I Automatic transfer from alert signal to alarm signal operates. Time:					
J Manual transfer from alert signal to alarm signal.					
K Automatic transfer from alert to alarm signal cancel (acknowledge) operates on a					
two stage system.					
L Alarm signal silence inhibit function operates.					
M Alarm signal manual silence operates.					
N Alarm signal silence visual indication operates					
Alarm signal and visible signal devices, when silenced, automatically reinitiate					
U upon subsequent alam.					
P Alarm signal silence automatic cut-out timer Time:					
Auditile visual, alert, and alarm signals programmed and operate as per					
manufacturer's design and specification.					
P Input circuit alarm and supervisory operation including audible and visual indicator					
operates.					
S Input circuit supervision fault causes a trouble indication.					
T Output circuit alarm indicators operate.					
U Output circuit supervision fault causes a trouble indication.					
V Visual indicator test (lamp test) operates.					
W Coded signal sequence operate not less than the required number of times and					
The correct alarm signal thereafter.					
Coded signal sequences are not interrupted by subsequent alarms.	\square				
Anchiary device control circuit is rated for the intended purpose.					
Anchiary device by-pass results in trouble signal.					
AA Appendix C5 12, Ancillary Device Circuit Test), for correct program operation as					
per design and specification.					
BB Fire alarm reset function operates.					
CC Main power to emergency power supply transfer operates.					
DD Control unit or transponder enclosure bonded to ground.					
EE Status change confirmation feature (smoke detectors only) verified.					
Recommended Additional Testing (not mandated by the Standard):	Yes	No	N/A		
Alarm, trouble, & supervisory relays function correctly.					
Is an AC disconnecting switch installed? YES NO					
(ULC CAN4-S524 restricts this, but some AHJ's will accept it.					

A "YES" answer here must be noted in the "Comments/Remarks" section of this report.)

Date:		🗌 Audit	🗌 Ve
Building Name:	Address:		

C5.2 Voice Communication Test Location: Identification: N/A Yes No Power 'on' visual indicator operates. А Common visual trouble signal operates. В С Common audible trouble signal operates. D Trouble signal silence switch operates. All-call voice paging, including visual indicator, operates. Е Output circuits for selective voice paging, including visual indication, F operates. Output circuits for selective voice paging trouble operation, including П G visual indication, operates. н Microphone, including press to talk switch, operates. Π Operation of voice paging does not interfere with initial inhibit time of alert L signal and alarm signal. J All-call voice paging operates (on emergency power supply). Upon failure of one amplifier, system automatically transfers to backup Κ amplifier(s). Circuits for emergency telephone call-in operation, including audible and L visual indication operates. Circuits for emergency telephones for operation, including two-way voice Μ П communication, operates. Circuits for emergency telephone trouble operation, including visual Ν П Π indication, operates. 0 П Emergency telephone verbal communication operates Ρ Emergency telephone operable or in-use tone at handset operates. While in standby mode, voice communication busses used for paging, alert signal, alarm signal, and emergency telephone communication Q circuits, an open circuit fault, or short circuit fault, or operation of an overcurrent protective device provided for the purpose, shall result in a specific trouble indication specific to the faulty buss. N/A Recommended Additional Testing (not mandated by the Standard): Yes No Visual indicator test (lamp test) operates. Main power to emergency power supply transfer operates. Communication control enclosure bonded to ground. Trouble signal on the voice communication system results in common trouble signal on the fire alarm system. Dead-front panel(s) in place & as per manufacturer's specification.

Address:	

rification

Date:	
Building	Name:

Address:

□ Audit □ Verification

	C5.3 Required System Response Times			
Contro	ol Unit/Transponder Field Location:			
Contr	rol Unit/Transponder Identification:			
00111		Yes	No	N/A
	Audible signal devices and visible signal devices operated within ten	_	_	
А	seconds and:			
	subsequent input operated within ten seconds.			
В	Remote connection operated within ten seconds.			
С	Release device start of sequence operated within ten seconds.			
	Required Annunciation operated within ten seconds			
D	and.			l l
_	subsequent input operation within ten seconds.			
	Required central alarm and control facility operated within ten seconds			
Е	and;			
	subsequent input operation within ten seconds.			
F	Ancillary circuits operated within ten seconds.			
Contro	ol Unit/Transponder Field Location:]
Contr	rol Unit/Transponder Identification:			-
Conti		Voc	No	NI/A
	Audible signal devices and visible signal devices operated within tan	162	NO	IN/A
Δ	seconds and.			
A	subsequent input operated within ten seconds			
B	Pomoto connection operated within ten seconds.			
D	Remote connection operated within ten seconds.			
C	Release device start of sequence operated within ten seconds.			
-	Required Annunciation operated within ten seconds			
D	and;			
	subsequent input operation within ten seconds.			
-	Required central alarm and control facility operated within ten seconds			
E	and;			
-	subsequent input operation within ten seconds.			\square
F	Ancillary circuits operated within ten seconds.			
F Contro Contr	Ancillary circuits operated within ten seconds. I Unit/Transponder Field Location: rol Unit/Transponder Identification:			
F Contro Contr	Subsequent input operation within ten seconds. Ancillary circuits operated within ten seconds. Unit/Transponder Field Location: rol Unit/Transponder Identification:	Yes	No	N/A
F Contro Contr	Subsequent input operation within ten seconds. Ancillary circuits operated within ten seconds. Ol Unit/Transponder Field Location: rol Unit/Transponder Identification: Audible signal devices and visible signal devices operated within ten	Yes	No	N/A
F Contro Contr A	Subsequent input operation within ten seconds. Ancillary circuits operated within ten seconds. Of Unit/Transponder Field Location: rol Unit/Transponder Identification: Audible signal devices and visible signal devices operated within ten seconds and; evenested within ten seconds	Yes	No	N/A
F Contro Contr A	Subsequent input operation within ten seconds. Ancillary circuits operated within ten seconds. Ol Unit/Transponder Field Location: rol Unit/Transponder Identification: Audible signal devices and visible signal devices operated within ten seconds and; subsequent input operated within ten seconds.	Yes	No	N/A
F Contro Contr A B	Subsequent input operation within ten seconds. Ancillary circuits operated within ten seconds. Ol Unit/Transponder Field Location: rol Unit/Transponder Identification: Audible signal devices and visible signal devices operated within ten seconds and; subsequent input operated within ten seconds. Remote connection operated within ten seconds. Product of the first seconds.	Yes	No	N/A
F Contro Contro A B C	Subsequent input operation within ten seconds. Ancillary circuits operated within ten seconds. Ol Unit/Transponder Field Location: rol Unit/Transponder Identification: Audible signal devices and visible signal devices operated within ten seconds and; subsequent input operated within ten seconds. Remote connection operated within ten seconds. Release device start of sequence operated within ten seconds.	Yes	No	N/A
F Contro Contro A B C	Subsequent input operation within ten seconds. Ancillary circuits operated within ten seconds. Ol Unit/Transponder Field Location: rol Unit/Transponder Identification: Audible signal devices and visible signal devices operated within ten seconds and; subsequent input operated within ten seconds. Remote connection operated within ten seconds. Release device start of sequence operated within ten seconds. Required Annunciation operated within ten seconds	Yes		N/A
F Contro Contro A B C D	Subsequent input operation within ten seconds. Ancillary circuits operated within ten seconds. Ol Unit/Transponder Field Location: rol Unit/Transponder Identification: Audible signal devices and visible signal devices operated within ten seconds and; subsequent input operated within ten seconds. Remote connection operated within ten seconds. Release device start of sequence operated within ten seconds. Required Annunciation operated within ten seconds and; audited annunciation operated within ten seconds.	Yes		N/A
F Contro Contro A B C D	Subsequent input operation within ten seconds. Ancillary circuits operated within ten seconds. Ol Unit/Transponder Field Location: rol Unit/Transponder Identification: Audible signal devices and visible signal devices operated within ten seconds and; subsequent input operated within ten seconds. Remote connection operated within ten seconds. Release device start of sequence operated within ten seconds. Required Annunciation operated within ten seconds. Required Annunciation operated within ten seconds. Beguired approximation operated within ten seconds. Description operation within ten seconds.	Yes		N/A
F Contro Contro A B C D	Subsequent input operation within ten seconds. Ancillary circuits operated within ten seconds. Ol Unit/Transponder Field Location: rol Unit/Transponder Identification: Audible signal devices and visible signal devices operated within ten seconds and; subsequent input operated within ten seconds. Remote connection operated within ten seconds. Release device start of sequence operated within ten seconds. Required Annunciation operated within ten seconds. Required central alarm and control facility operated within ten seconds.	Yes		N/A
F Contro Contro A B C D E	Subsequent input operation within ten seconds. Ancillary circuits operated within ten seconds. Ol Unit/Transponder Field Location: rol Unit/Transponder Identification: Audible signal devices and visible signal devices operated within ten seconds and; subsequent input operated within ten seconds. Remote connection operated within ten seconds. Release device start of sequence operated within ten seconds. Required Annunciation operated within ten seconds. Required central alarm and control facility operated within ten seconds and; subsequent input operation within ten seconds.	Yes		N/A
F Contro Contro A B C D E	Subsequent input operation within ten seconds. Ancillary circuits operated within ten seconds. Ol Unit/Transponder Field Location: rol Unit/Transponder Identification: Audible signal devices and visible signal devices operated within ten seconds and; subsequent input operated within ten seconds. Remote connection operated within ten seconds. Release device start of sequence operated within ten seconds. Required Annunciation operated within ten seconds. Required central alarm and control facility operated within ten seconds and; subsequent input operation within ten seconds. Required central alarm and control facility operated within ten seconds and; subsequent input operation within ten seconds.	Yes		N/A
F Contro Contro A B C D E F	Subsequent input operation within ten seconds. Ancillary circuits operated within ten seconds. Ol Unit/Transponder Field Location: rol Unit/Transponder Identification: Audible signal devices and visible signal devices operated within ten seconds and; subsequent input operated within ten seconds. Remote connection operated within ten seconds. Release device start of sequence operated within ten seconds. Required Annunciation operated within ten seconds. Required central alarm and control facility operated within ten seconds and; subsequent input operation within ten seconds. Required central alarm and control facility operated within ten seconds and; subsequent input operation within ten seconds. Required central alarm and control facility operated within ten seconds and; subsequent input operation within ten seconds. Ancillary circuits operated within ten seconds.	Yes		N/A
F Contro Contro A B C D E F	Subsequent input operation within ten seconds. Ancillary circuits operated within ten seconds. Ol Unit/Transponder Field Location: rol Unit/Transponder Identification: Audible signal devices and visible signal devices operated within ten seconds and; subsequent input operated within ten seconds. Remote connection operated within ten seconds. Release device start of sequence operated within ten seconds. Required Annunciation operated within ten seconds. Required central alarm and control facility operated within ten seconds and; subsequent input operation within ten seconds. Required central alarm and control facility operated within ten seconds and; subsequent input operation within ten seconds. Required central alarm and control facility operated within ten seconds and; subsequent input operation within ten seconds. Ancillary circuits operated within ten seconds.	Yes		N/A
F Contro Contro A B C D E F Contro	Subsequent input operation within ten seconds. Ancillary circuits operated within ten seconds. Ol Unit/Transponder Field Location: rol Unit/Transponder Identification: Audible signal devices and visible signal devices operated within ten seconds and; subsequent input operated within ten seconds. Remote connection operated within ten seconds. Release device start of sequence operated within ten seconds. Required Annunciation operated within ten seconds. Required central alarm and control facility operated within ten seconds and; subsequent input operation within ten seconds. Required central alarm and control facility operated within ten seconds and; subsequent input operation within ten seconds. Required central alarm and control facility operated within ten seconds and; subsequent input operation within ten seconds. Ancillary circuits operated within ten seconds. Ancillary circuits operated within ten seconds.	Yes		
F Contro Contro A B C D E F Contro Contro	Subsequent input operation within ten seconds. Ancillary circuits operated within ten seconds. Pl Unit/Transponder Field Location: rol Unit/Transponder Identification: Audible signal devices and visible signal devices operated within ten seconds and; subsequent input operated within ten seconds. Remote connection operated within ten seconds. Release device start of sequence operated within ten seconds. Required Annunciation operated within ten seconds. Required central alarm and control facility operated within ten seconds and; subsequent input operation within ten seconds. Required central alarm and control facility operated within ten seconds and; subsequent input operation within ten seconds. Ancillary circuits operated within ten seconds. Ancillary circuits operated within ten seconds. Ol Unit/Transponder Field Location: rol Unit/Transponder Field Location:	Yes		
F Contro Contro A B C D E F Contro Contro	Subsequent input operation within ten seconds. Ancillary circuits operated within ten seconds. Pl Unit/Transponder Field Location: rol Unit/Transponder Identification: Audible signal devices and visible signal devices operated within ten seconds and; subsequent input operated within ten seconds. Remote connection operated within ten seconds. Release device start of sequence operated within ten seconds. Required Annunciation operated within ten seconds. Required central alarm and control facility operated within ten seconds and; subsequent input operation within ten seconds. Required central alarm and control facility operated within ten seconds and; subsequent input operation within ten seconds. Ancillary circuits operated within ten seconds. Ancillary circuits operated within ten seconds. Ol Unit/Transponder Field Location: rol Unit/Transponder Identification:	Yes	No □ □ □ □ □ □ □ □ □ □ □ □ □	N/A
F Contro Contro A B C D E F Contro Contro	Subsequent input operation within ten seconds. Ancillary circuits operated within ten seconds. PI Unit/Transponder Field Location: rol Unit/Transponder Identification: Audible signal devices and visible signal devices operated within ten seconds and; subsequent input operated within ten seconds. Remote connection operated within ten seconds. Release device start of sequence operated within ten seconds. Required Annunciation operated within ten seconds. Required central alarm and control facility operated within ten seconds and; subsequent input operation within ten seconds. Required central alarm and control facility operated within ten seconds and; subsequent input operation within ten seconds. Ancillary circuits operated within ten seconds. Audible signal devices and visible signal device	Yes	No □ □ □ □ □ □ □ □ □ □ □ □ □	N/A
F Contro Contro A B C D E F Contro Contro Contro	Subsequent input operation within ten seconds. Ancillary circuits operated within ten seconds. PI Unit/Transponder Field Location: rol Unit/Transponder Identification: Audible signal devices and visible signal devices operated within ten seconds and; subsequent input operated within ten seconds. Remote connection operated within ten seconds. Required Annunciation operated within ten seconds. Required Annunciation operated within ten seconds. Required central alarm and control facility operated within ten seconds and; subsequent input operation within ten seconds. Required central alarm and control facility operated within ten seconds and; subsequent input operation within ten seconds. Ancillary circuits operated within ten seconds. Audible signal devices and visible signal devices operated	Yes		N/A
F Contro Contro A B C D E F Contro Contro Contro	Subsequent input operation within ten seconds. Ancillary circuits operated within ten seconds. Ol Unit/Transponder Field Location: rol Unit/Transponder Identification: Audible signal devices and visible signal devices operated within ten seconds and; subsequent input operated within ten seconds. Remote connection operated within ten seconds. Required Annunciation operated within ten seconds. Required Annunciation operated within ten seconds. Required central alarm and control facility operated within ten seconds and; subsequent input operation within ten seconds. Required central alarm and control facility operated within ten seconds and; subsequent input operation within ten seconds. Ancillary circuits operated within ten seconds. Audible signal devices and visible signal devices operated within ten seconds and; subsequent input operated within ten seconds.	Yes		N/A
F Contro Contro A B C D E F Contro Contro Contro A B	Subsequent input operation within ten seconds. Ancillary circuits operated within ten seconds. Ol Unit/Transponder Field Location: rol Unit/Transponder Identification: Audible signal devices and visible signal devices operated within ten seconds and; subsequent input operated within ten seconds. Remote connection operated within ten seconds. Release device start of sequence operated within ten seconds and; subsequent input operation within ten seconds. Required central alarm and control facility operated within ten seconds and; subsequent input operation within ten seconds. Required central alarm and control facility operated within ten seconds and; subsequent input operation within ten seconds. Ancillary circuits operated within ten seconds. Audible signal devices and visible signal devices operated within ten seconds and; subsequent input operated within ten seconds. Remote connection operated within ten seconds. Remote connection operated within ten seconds. Remote connection operated within ten seconds.	Yes		N/A
F Contro Contro A B C D E F Contro Contro Contro Contro Contro Contro	Subsequent input operation within ten seconds. Ancillary circuits operated within ten seconds. Ol Unit/Transponder Field Location: rol Unit/Transponder Identification: Audible signal devices and visible signal devices operated within ten seconds and; subsequent input operated within ten seconds. Remote connection operated within ten seconds. Required Annunciation operated within ten seconds. Required central alarm and control facility operated within ten seconds and; subsequent input operation within ten seconds. Required central alarm and control facility operated within ten seconds and; subsequent input operation within ten seconds. Ancillary circuits operated within ten seconds. Andible signal devices and visible signal devices operated within ten seconds. Audible signal devices and visible signal devices operated within ten seconds. Remote connection operated within ten seconds. Remo	Yes		N/A
F Contro Contro A B C D E F Contro Contro Contro A B C	Subsequent input operation within ten seconds. Ancillary circuits operated within ten seconds. Ol Unit/Transponder Field Location: rol Unit/Transponder Identification: Audible signal devices and visible signal devices operated within ten seconds and; subsequent input operated within ten seconds. Remote connection operated within ten seconds. Required Annunciation operated within ten seconds. Required central alarm and control facility operated within ten seconds and; subsequent input operation within ten seconds. Required central alarm and control facility operated within ten seconds and; subsequent input operation within ten seconds. Ancillary circuits operated within ten seconds. Andible signal devices and visible signal devices operated within ten seconds. Audible signal devices and visible signal devices operated within ten seconds. Remote connection operated within ten seconds. Remote connection operated within ten seconds. Release device start of sequence operated within ten seconds. Release device start of sequence operated within ten seconds.	Yes		N/A
F Contro Contro A B C D E F Contro Co	subsequent input operation within ten seconds. Ancillary circuits operated within ten seconds. ol Unit/Transponder Field Location: rol Unit/Transponder Identification: Audible signal devices and visible signal devices operated within ten seconds and; subsequent input operated within ten seconds. Remote connection operated within ten seconds. Required Annunciation operated within ten seconds. Required Annunciation operated within ten seconds. Required central alarm and control facility operated within ten seconds and; subsequent input operation within ten seconds. Required central alarm and control facility operated within ten seconds and; subsequent input operated within ten seconds. Ancillary circuits operated within ten seconds. Ol Unit/Transponder Field Location: rol Unit/Transponder Identification: Audible signal devices and visible signal devices operated within ten seconds. Audible signal devices and visible signal devices operated within ten seconds. Remote connection operated within ten seconds. Remote connection operated within ten seconds. Remote connection operated within ten seconds. Reduired Annunciation operated within ten seconds. Required Annunciation operated within ten seconds. Required Annunciat	Yes		N/A
F Contro Contro C D E F Contro Contro Contro Contro Contro Contro Contro Contro Contro Contro Contro Contro Contro Contro D	subsequent input operation within ten seconds. Ancillary circuits operated within ten seconds. ol Unit/Transponder Field Location: rol Unit/Transponder Identification: Audible signal devices and visible signal devices operated within ten seconds and; subsequent input operated within ten seconds. Remote connection operated within ten seconds. Release device start of sequence operated within ten seconds and; subsequent input operation within ten seconds. Required Annunciation operated within ten seconds. Required central alarm and control facility operated within ten seconds and; subsequent input operation within ten seconds. Ancillary circuits operated within ten seconds. Ancillary circuits operated within ten seconds. Ancillary circuits operated within ten seconds. Antillary circuits operated within ten seconds. Audible signal devices and visible signal devices operated within ten seconds. Audible signal devices and visible signal devices operated within ten seconds. Remote connection operated within ten seconds. Remote connection operated within ten seconds. Remote connection operated within ten seconds. Release device start of sequence operated within ten seconds. Release device start of sequence operated within ten seconds. <	Yes		N/A
F Contro Contro A B C D E F Contro Contro Contro Contro Contro Contro Contro Contro Contro	subsequent input operation within ten seconds. Ancillary circuits operated within ten seconds. of Unit/Transponder Field Location: rol Unit/Transponder Identification: Audible signal devices and visible signal devices operated within ten seconds and; subsequent input operated within ten seconds. Remote connection operated within ten seconds. Release device start of sequence operated within ten seconds and; subsequent input operation within ten seconds. Required Annunciation operated within ten seconds. Required central alarm and control facility operated within ten seconds and; subsequent input operation within ten seconds. Ancillary circuits operated within ten seconds. Audible signal devices and visible signal devices operated within ten seconds and; subsequent input operated within ten seconds. Remote connection operated within ten seconds. Remote connection operated within ten seconds. Remote connection operated within ten seconds. Required Annunciation operated within ten seconds. Requir	Yes		N/A N/A
F Contro Contro C D E F Contro Contro Contro Contro Contro Contro Contro Contro Contro Contro Contro Contro Contro Contro E E E E E E E E E E E E E E E E E E E	Subsequent input operation within ten seconds. Ancillary circuits operated within ten seconds. Init/Transponder Field Location: rol Unit/Transponder Identification: Audible signal devices and visible signal devices operated within ten seconds and; subsequent input operated within ten seconds. Remote connection operated within ten seconds. Release device start of sequence operated within ten seconds. Required Annunciation operated within ten seconds. Required central alarm and control facility operated within ten seconds and; subsequent input operation within ten seconds. Ancillary circuits operated within ten seconds. Andible signal devices and visible signal devices operated within ten seconds and; subsequent input operated within ten seconds. Remote connection operated within ten seconds. Remote connection operated within ten seconds. Reduible signal devices and visible signal devices operated within ten seconds. Required contral operated within ten seconds. Required connectio	Yes		N/A N/A
F Contro Contro C D E F Contro	Subsequent input operation within ten seconds. Ancillary circuits operated within ten seconds. I Unit/Transponder Field Location: rol Unit/Transponder Identification: Audible signal devices and visible signal devices operated within ten seconds and; subsequent input operated within ten seconds. Remote connection operated within ten seconds. Required Annunciation operated within ten seconds. Required Annunciation operated within ten seconds. Required central alarm and control facility operated within ten seconds and; subsequent input operation within ten seconds. Ancillary circuits operated within ten seconds. Audible signal devices and visible signal devices operated within ten seconds. Remote connection operated within ten seconds. Renote connection operated within ten seconds. Release device start of sequence operated within ten seconds. Required Annunciation operated within ten seconds. Required Annunciation operated within ten	Yes		

Date:] /	Audit	Verification
Building Name:	Address:			

C5.4 Control Unit or Transponder Inspection					
Contro	l Unit/Transponder Field Location:				
Contr	ol Unit/Transponder Identification:				
		Yes	No	N/A	
А	Input circuit designations correctly identified in relation to connected field devices.				
В	Output circuit designations correctly identified in relation to connected field devices.				
С	Correct designations for common control functions and indicators.				
D	Plug-in components and modules securely in place.				
Е	Plug-in cables securely in place.				
	Record the date, revision and version of firmware:				
-	Date: Revision: Version:				
Г	Record the date, revision and version of the program software:				
	Date: Revision: Version:				
G	Control unit/transponder is clean and free of dust and dirt.				
Н	Fuses in accordance with the manufacturer's specification.				
I	Control unit/transponder lock is functional.				
J	Termination points for wiring to field devices secure.				
к	Control unit/transponder power disconnects in accordance with C22.1, Safety Standard for Electrical Installations, Canadian Electrical Code, Part 1.				
L	Field wiring entry points for the various circuits and circuit separations are in accordance with the manufacturer's installation instructions.				
М	Main power supply feed wiring is in accordance with the manufacturer's specifications.				
N	Verify control units/transponders with stand alone capability serve the same area for both input circuits and output circuits.				
0	Control units or transponders which operate with stand alone capability have signal silence, reset, and trouble silence switches with visual indications, degraded mode capability and stand alone capability indicators.				
Р	Each control unit/transponder has been furnished with installation, operating and maintenance instructions.				
Q	Control unit/transponder visual indicators comply with Table 3 – Visual Indicators Colour Code.				
Recom	mended Additional Visual Inspection (not mandated by the Standard):	Yes	No	N/A	
Dead-fr	ont panel(s) in place & as per manufacturer's specification.				

_

Date:		Audit	Verification
Building Name:	Address:		

C5.5 Large Scale Network Systems					
		Yes	No	N/A	
А	Verify control units/transponders serve the same area for both input circuits and output circuits.				
В	Verify control units/transponders with stand alone capability have signal silence, reset, and trouble silence switches with visual indicators, degraded mode capability and stand alone capability indicators.				
с	Confirm that between any nodes a single open circuit fault, wire-to-wire short circuit fault, or ground fault on the network results in a trouble signal at each node and continued alarm receipt capability at each node under these conditions.				
D	To test stand alone capability, create a condition of data communication link failure, and confirm each control unit or transponder is capable of receiving an alarm initiation and provides output operation in the area as served by the control unit or transponder in degraded mode.				
E	To test degraded mode capability, create a condition of data communication link failure in two separate locations creating two network segments, and confirm each segment of the network has the following operation:(i)Operate the alarm signals in accordance with the system operating sequence;(ii)Maintain synchronization of control units or transponders for alert signals and alarm signals;(iii)Operate local relays in control units or transponders connected to ancillary devices as required;				
	 (iv) (iv) Confirm the operation of acknowledge, signal silence, reset and trouble silence switches with visual indicators, degraded mode capability and stand alone capability indicators are functional for each network segment. 				

Date: Building Name:

Address:

Verification

Audit

	Power Supply Field Location:			
	Power Supply Identification:			
	Circuit Disconnect Means Location:			
	Circuit Panel/Breaker Identification:			
		Yes	No	N/A
А	Conforms with the requirements of CAN/ULC-S524, Standard for the Installation of Fire Alarm Systems; and C22.1, Safety Standard for Electrical Installations, Canadian Electrical Code, Part 1, Section 32.			
В	Fused in accordance with the manufacturer's marked rating of the system.			
С	Equipped with the identified disconnect means.			
D	Adequate to meet the requirements of the system.			
E	Power for ancillary devices is taken from a source separate from the fire alarm system control			
-	unit or transponder power supply. Power for ancillary devices is taken from the control unit or transponder that is designed to			
F	provide such power.			
G	Ancillary devices, which are powered from the control unit or transponder, are recorded.			
н	Where fault isolation in power distribution riser has been provided, tests have been conducted to ensure a wire-to-wire short in the field wiring between each pair of control units or transponders, in turn, results in annunciation of the fault and continued operation outside of the shorted section confirmed.			
Recor	mmended Additional Visual Inspection (not mandated by the Standard):	Yes	No	N/A
Jead-	tront panel(s) in place & as per manufacturer's specification.			
Circui	t disconnect means painted RED and locked "on".	<u> </u>	느끔	
ower	r supply cabinet (where applicable) is clean and free of dust and dirt.			
		V DI I D'J		
R	Battery Capacity (as installed): Sealed Lead Acid INI-Cad Internation V Battery Capacity (as installed): AH equired Building Code Alarm Operation: 30 minutes 120 minutes	vet Lea	a	
R	Battery Capacity (as installed): Sealed Lead Acid In-Cad Internation IV Battery Capacity (as installed): AH Lequired Building Code Alarm Operation: 30 minutes 120 minutes	Yes	No	N/A
R	Battery Capacity (as installed): Sealed Lead Acid In-Cad Introduction IV Battery Capacity (as installed): AH equired Building Code Alarm Operation: 30 minutes 120 minutes	Yes	No	N/A
R A B	Battery Type (as installed): Sealed Lead Acid NI-Cad Eltrium-ion V Battery Capacity (as installed):	Yes	No	N/A
R A B C	Battery Type (as installed): Sealed Lead Acid NI-Cad Litrium-Ion V Battery Capacity (as installed):	Yes	No	N/A
R A B C D	Battery Type (as installed): Sealed Lead Acid NI-Cad Litrium-Ion V Battery Capacity (as installed):	Yes	O No	N/A
R B C D	Battery Type (as installed): Sealed Lead Acid NI-Cad Lithium-Ion V Battery Capacity (as installed): AH AH Required Building Code Alarm Operation: 30 minutes 120 minutes Correct battery type as recommended by the manufacturer. Correct battery rating as determined by battery calculations based on full system load. Battery voltage (main power "on"): VDC Battery voltage – main power "off" – FAS in supervisory condition: VDC Battery current - main power "off" – FAS in supervisory condition: mA	Yes	O No	N/A
R B C D	Battery Type (as installed):	Yes	a No	N/A
R B C D	Battery Capacity (as installed): Sealed Lead Acid NI-Cad Elinium-ion V Battery Capacity (as installed): AH Required Building Code Alarm Operation: 30 minutes 120 minutes Correct battery type as recommended by the manufacturer. Correct battery rating as determined by battery calculations based on full system load. Battery voltage (main power "on"): VDC Battery voltage – main power "off" – FAS in supervisory condition: VDC Battery voltage – main power "off" – FAS in full load ALARM: VDC Battery current – main power "off" – FAS in full load ALARM: VDC Battery unrent – main power "off" – FAS in full load ALARM: A	Yes	a No	N/A
R B C D E	Battery Capacity (as installed): Sealed Lead Acid NI-Cad Elinium-ion V Battery Capacity (as installed): AH Required Building Code Alarm Operation: 30 minutes 120 minutes Correct battery type as recommended by the manufacturer. Correct battery rating as determined by battery calculations based on full system load. Battery voltage (main power "on"): VDC Battery voltage – main power "off" – FAS in supervisory condition: VDC Battery voltage – main power "off" – FAS in supervisory condition: mA Battery voltage – main power "off" – FAS in full load ALARM: VDC Battery current – main power "off" – FAS in full load ALARM: MA Battery charging current (main power "on"): mA Battery charging current (main power "on"): mA		a No	N/A
R B C D E F G	Battery Type (as installed): Sealed Lead Acid NI-Cad Elinium-Ion V Battery Capacity (as installed): AH Required Building Code Alarm Operation: 30 minutes 120 minutes Correct battery type as recommended by the manufacturer. Correct battery rating as determined by battery calculations based on full system load. Battery voltage (main power "on"): VDC Battery current - main power "off" - FAS in supervisory condition: VDC Battery voltage - main power "off" - FAS in full load ALARM: VDC Battery current - main power "off" - FAS in full load ALARM: A Battery charging current (main power "on"): mA Inspected for physical damage. Torminable domaged and lubiticated		No	N/A
R B C D F G H	Battery Type (as installed): Sealed Lead Acid NI-Cad Elititum-Ion V Battery Capacity (as installed): AH AH Required Building Code Alarm Operation: 30 minutes 120 minutes Correct battery type as recommended by the manufacturer. Correct battery rating as determined by battery calculations based on full system load. Battery voltage (main power "on"): VDC Battery voltage – main power "off" – FAS in supervisory condition: VDC Battery voltage – main power "off" – FAS in supervisory condition: mA Battery voltage – main power "off" – FAS in full load ALARM: VDC Battery current – main power "off" – FAS in full load ALARM: VDC Battery charging current (main power "on"): mA Inspected for physical damage. Terminals cleaned and lubricated. Terminals cleaned and lubricated. Terminals cleaned and lubricated.	Yes		N/A
R B C D E F G H	Battery Type (as installed): Sealed Lead Acid NI-Cad Litrium-Ion V Battery Capacity (as installed): AH AH Required Building Code Alarm Operation: 30 minutes 120 minutes Correct battery type as recommended by the manufacturer. Correct battery rating as determined by battery calculations based on full system load. Battery voltage (main power "on"): VDC Battery voltage – main power "off" – FAS in supervisory condition: VDC Battery voltage – main power "off" – FAS in supervisory condition: mA Battery voltage – main power "off" – FAS in full load ALARM: VDC Battery current – main power "off" – FAS in full load ALARM: VDC Battery current – main power "off" – FAS in full load ALARM: A Battery charging current (main power "on"): mA Inspected for physical damage. Terminals cleaned and lubricated. Terminals clamped tightly. Correct electrolyte level	Yes		N/A
R A B C D D E F G H I J K	Battery Type (as installed): Sealed Lead Acid NI-Cad Lithium-Ion V Battery Capacity (as installed): AH AH Required Building Code Alarm Operation: 30 minutes 120 minutes Correct battery type as recommended by the manufacturer. Correct battery rating as determined by battery calculations based on full system load. Battery voltage (main power "on"): VDC Battery voltage – main power "off" – FAS in supervisory condition: VDC Battery voltage – main power "off" – FAS in supervisory condition: mA Battery voltage – main power "off" – FAS in supervisory condition: MA Battery voltage – main power "off" – FAS in full load ALARM: VDC Battery current – main power "off" – FAS in full load ALARM: VDC Battery charging current (main power "on"): mA Inspected for physical damage. Terminals cleaned and lubricated. Terminals clamped tightly. Correct electrolyte level. Specific gravity of the electrolyte is within the battery manufacturer's specifications			N/A
R A B C C D C C D C C C C C C C C C C C C C	Battery Type (as installed): Sealed Lead Acid NI-Cad Lithium-Ion V Battery Capacity (as installed):			N/A
R A B C C D E F G H I J K L	Battery Type (as installed): Sealed Lead Acid IN-Cad Elinium-Ion IV Battery Capacity (as installed): AH AH Required Building Code Alarm Operation: 30 minutes 120 minutes Correct battery type as recommended by the manufacturer. VDC Correct battery rating as determined by battery calculations based on full system load. VDC Battery voltage (main power "on"): VDC Battery current - main power "off" – FAS in supervisory condition: VDC Battery voltage – main power "off" – FAS in full load ALARM: VDC Battery current - main power "off" – FAS in full load ALARM: VDC Battery current - main power "off" – FAS in full load ALARM: VDC Battery current - main power "off" – FAS in full load ALARM: A Battery charging current (main power "on"): mA Inspected for physical damage. Terminals cleaned and lubricated. Terminals clamped tightly. Correct electrolyte level. Specific gravity of the electrolyte is within the battery manufacturer's specifications. Inspected for electrolyte leakage. Adequately wentilated Adequately wentilated Adequately wentilated			N/A
R B C C D E F G H I J K L M N	Battery Type (as installed):			N/A
R A B C D E F G H I J K L M N O	Battery Type (as installed):			N/A
R A B C D E F G H I J K L L M N O	Battery rype (as installed): Sealed Lead Add INI-Cad Lithiumi-ion V Battery Capacity (as installed): AH Required Building Code Alarm Operation: 30 minutes 120 minutes Correct battery type as recommended by the manufacturer. Correct battery rating as determined by battery calculations based on full system load. Battery voltage (main power "on"): VDC Battery voltage – main power "off" – FAS in supervisory condition: VDC Battery voltage – main power "off" – FAS in supervisory condition: mA Battery voltage – main power "off" – FAS in supervisory condition: mA Battery voltage – main power "off" – FAS in full load ALARM: VDC Battery current – main power "off" – FAS in full load ALARM: A Battery charging current (main power "on"): mA Inspected for physical damage. mA Inspected for physical damage. mA Terminals cleaned and lubricated. Terminals cleaned tightly. Correct electrolyte level. Specific gravity of the electrolyte is within the battery manufacturer's specifications. Inspected for electrolyte leakage. Adequately ventilated. Record manufacturer's date code or in-service date: Disconnection causes trouble signal.			N/A
R A B C D E F G H I J K L M N O	Battery Type (as installed): Sealed Lead Acid INI-Cad Lininiti-Ion V Battery Capacity (as installed):			
R B C D E F G H I J K L M N O O	Battery Type (as installed):			
R A B C D E F G H I J K L U M N O O	Battery Capacity (as installed): Sealed Lead Acid Ni-Cad Lithiuminion V Battery Capacity (as installed): 30 minutes 120 minutes Correct battery type as recommended by the manufacturer. Correct battery rating as determined by battery calculations based on full system load. Battery voltage (main power "on"): VDC Battery voltage – main power "off" – FAS in supervisory condition: VDC Battery voltage – main power "off" – FAS in full load ALARM: VDC Battery voltage – main power "off" – FAS in full load ALARM: VDC Battery current – main power "off" – FAS in full load ALARM: VDC Battery charging current (main power "on"): mA Inspected for physical damage. Terminals cleaned and lubricated. Terminals cleaned and lubricated. Terminals cleaned and lubricated. Terminals cleaned tightly. Correct electrolyte level. Specific gravity of the electrolyte is within the battery manufacturer's specifications. Inspected for electrolyte leakage. Adequately ventilated. Record manufacturer's date code or in-service date: Disconnection causes trouble signal. Indicate type of tests performed on a fully charged battery: (i) Required supervisory load for 24 h followed by the required full load operation <			
R A B C D E F G H I J K L U M N O O	Battery Type (as installed):			
R A B C D E F G H I J K L M N O O P R	Battery type (as installed):			N/A
R A B C D E F G H I J K L M N O P P Q R S	Battery Type (as installed):			N/A
R A B C D E F G H I J K L U M N O O P Q R S T	Battery Type (as installed):			
R A B C D E F G H I J K L M N O O R S T U	Battery Capacity (as installed): Sealed Lead Acid AH Battery Capacity (as installed): AH Lequired Building Code Alarm Operation: 30 minutes 120 minutes Correct battery type as recommended by the manufacturer. VDC Correct battery rating as determined by battery calculations based on full system load. VDC Battery voltage – main power "off" – FAS in supervisory condition: VDC Battery current - main power "off" – FAS in full load ALARM: VDC Battery current - main power "off" – FAS in full load ALARM: A Battery current - main power "off" – FAS in full load ALARM: A Battery current - main power "off" – FAS in full load ALARM: A Battery charging current (main power "on"): mA Inspected for physical damage. mmanufacturer's specific ations. Terminals clamped tightly. Correct electrolyte level. Specific gravity of the electolyte is within the battery manufacturer's specifications. Inspected for electrolyte leakage. Adequately ventilated. Record manufacturer's date code or in-service date: Disconnection causes trouble signal. Indicate type of tests performed on a fully charged battery: (i) Required supervisory load for 24 h followed by the required full load operation			

Date: □ Verification Audit **Building Name:** Address:

Annunciator Identification: Annunciator Identification: Yes No N/A A Power "on" indicator operates. Image: Ima		C5.8 ANNUNCIATOR AND DISPLAY AND CONTROL CENTRE TEST AND IN	ISPEC	ΓΙΟΝ	
Annunciator Identification: Yes No NA A Power "on" indicator operates. Image: Comparison of the expension of the expensis		Annunciator Location:			
A Power "on" indicator operates. Ves No N/A B Individual alarm and supervisory input zone clearly indicated and separately □ □ C Individual alarm and supervisory input zone designation labels are properly identified. □ □ D actual field coation. □ □ □ E Common trouble signal operates. □		Annunciator Identification:	-		
A Power' on' indicator operates.			Yes	No	N/A
B Individual altam and supervisory input zone designation labels are properly identified.	A	Power "on" indicator operates.			
C Individual alarm and supervisory input zone designation labels are properly identified.	В	Individual alarm and supervisory input zone clearly indicated and separately designated.			
Where active and supporting field devices are utilized, device labels correspond with Image: Common trouble signal operates. E Common trouble signal operates. Image: Common trouble signal operates.	С	Individual alarm and supervisory input zone designation labels are properly identified.			
E Common trouble signal operates.	D	Where active and supporting field devices are utilized, device labels correspond with actual field location.			
F Visual indicator test (lamp test) operates.	E	Common trouble signal operates.			
Input wing from control unit or transponder is supervised and of the correct type and give in accordance with the equipment manufacturer's installation wiring requirements. Image: Control Content Control Control Control Control Control Control Cont	F	Visual indicator test (lamp test) operates.			
H Alarm signal silence visual indicator operates.	G	Input wiring from control unit or transponder is supervised and of the correct type and gauge in accordance with the equipment manufacturer's installation wiring requirements.			
1 Switches for ancillary functions operates as per design and specification.	Н	Alarm signal silence visual indicator operates.			
J Ancillary functions visual indicators operates.	I	Switches for ancillary functions operate as per design and specification.			
K Manual activation of alarm signal and indication operates.	J	Ancillary functions visual indicators operates.			
L Displays are visible in the installed location. Image: Construction of the installed location. M Operates on emergency power. Image: Construction of the installed location. N Visual indicators comply with Table 3 – Visual indicators Colour Code Image: Construction of the installed location. O Sequential Displays), where utilized. Image: Construction of the installed location. Annunciator/Sequential Display location: Annunciator/Sequential Display location: Annunciator/Sequential Display location: Individual airm and supervisory zone indication operates. Exception: Operation of each individual alarm and supervisory zone indication gives the identical indication, or lights the identical indicators at the other annunciator(s) Image: Construction of each individual alarm and supervisory zone tested per annunciator or sequential display to confirm operation. C Individual alarm and supervisory input zone designation labels are properly identified. Image: Construction operates. F Visual indicator control unit or transponder is supervised and of the correct type and gauge in accordance with the equipment manufacturer's installation wiring requirements. Image: Construction operates. F Visual indicator operates. Imput wiring from control unit or transponder is supervised and of the correct type and gauge in accordance with the equipment manufacturer's installation wiring requirements. Imput wiring from contro	K	Manual activation of alarm signal and indication operates.			
M Operates on emergency power. Image: Comply with Table 3 - Visual indicators Colour Code Image: Comply with Table 3 - Visual indicators Colour Code Image: Comply with Table 3 - Visual indicators Colour Code Image: Comply with Table 3 - Visual indicators Colour Code Image: Comply with Table 3 - Visual indicators Colour Code Image: Comply with Table 3 - Visual indicators or Sequential Display operates as per Appendix C5.9 (Annunciators or Sequential Display Location: Annunciator/Sequential Display Location: Annunciator/Sequential Display Location: Image: Comply with Table 3 - Visual indicator operates. Exception: Operation of each individual alarm and supervisory zone indication gives the identical indicator, or lights the identical indicators at the other annunciator(s) and sequential display (s). Image: Comply with Table 3 - Visual indicator or sequential display to confirm operation. C Individual alarm and supervisory input zone designation labels are properly identified. Image: Comply with 1 - Comply with 1 - Comply with 1 - Comply with 1 - Compond wi	L	Displays are visible in the installed location.			
N Visual indicators comply with Table 3 - Visual indicators Colour Code	M	Operates on emergency power.			\square
O Multi-line sequential Display operates as per Appendix C5.9 (Annunciators of Sequential Displays), where utilized. C5.9 ANNUNCIATORS OR SEQUENTIAL DISPLAYS Annunciator/Sequential Display Location: Annunciator/Sequential Display Identification: Yes No A Power "on" indicator operates. Individual alarm and supervisory zone indication operates. Exception: Operation of each individual alarm and supervisory zone indication gives the identical indication, or lights the identical indicators at the other annunciator(s) and sequential display(s). Specify method of confirmation: Iminimum of one alarm zone and one supervisory zone tested per annunciator or sequential display to confirm operates. C Individual alarm and supervisory input zone designation labels are properly identified. D Where active and supporting field devices are utilized, device labels correspond with actual field location. E Common trouble signal operates. F Visual indicator test (lamp test) operates. Input wiring from control unit or transponder is supervised and of the correct type and gage in accordance with the equipment manufacturer's installation wiring requirements. H Alarm signal silence visual indicator operates. I Switches for ancillary functions operate as per design and specification. J Ancillary fu	N	Visual indicators comply with Table 3 – Visual indicators Colour Code			
C5.9 ANNUNCIATORS OR SEQUENTIAL DISPLAYS Annunciator/Sequential Display Location: Annunciator/Sequential Display Identification: Yes No A Power 'on' indicator operates. Individual alarm and supervisory zone indication operates. Image: Colspan="2">Colspan="2"Colspan="2"Colspan="2"Colspan="2"Colspan="2"Colsp	0	Sequential Displays), where utilized.			
Annunciator/Sequential Display Location: Annunciator/Sequential Display Identification: Yes No NA A Power "on" indicator operates. Individual alarm and supervisory zone indication operates. Individual alarm and supervisory zone indication operates. Individual alarm and supervisory zone indication operates. Exception: Operation of each individual alarm and supervisory zone indication gives the identical indication, or lights the identical indications at the other annunciator(s) Imdividual alarm and supervisory zone tested per annunciator or sequential display to confirm operation. Imdividual alarm and supervisory input zone designation labels are properly identified. Imdividual alarm and supervisory input zone designation labels correspond with actual field location. Imdividual alarm and supervisory input zone designation labels are properly identified. Imdividual alarm and supervisory input zone designation labels are properly identified. Imdividual alarm and supervisory input zone designation labels are properly identified. Imdividual alarm and supervisory input zone designation labels are properly identified. Imdividual alarm and supervisory input zone designation labels are properly identified. Imdividual alarm and supervisory input zone designation labels are properly identified. Imdividual alarm and supervisory input zone designation labels are properly identified. Imdividual alarm and supervisory input zone designation labels are properly identified. Imdividual alarm and supervisory input zone designation labels are properly identified. Imdividual		C5.9 ANNUNCIATORS OR SEQUENTIAL DISPLAYS			
Annunciator/Sequential Display Identification: Yes No N/A A Power "on" indicator operates.		Annunciator/Sequential Display Location:			
Yes No N/A A Power "on" indicator operates.	Annu	nciator/Sequential Display Identification:			
A Power "on" indicator operates.			Yes	No	N/A
Individual alarm and supervisory zone indication operates.	A	Power "on" indicator operates.			
Exception: Operation of each individual alarm and supervisory zone indication gives the identical indication, or lights the identical indicators at the other annunciator(s) and sequential display(s). Specify method of confirmation: Minimum of one alarm zone and one supervisory zone tested per annunciator or sequential display to confirm operation. Individual alarm and supervisory input zone designation labels are properly identified. Individual alarm and supervisory input zone designation labels are properly identified. Where active and supporting field devices are utilized, device labels correspond with actual field location. Common trouble signal operates. Input wiring from control unit or transponder is supervised and of the correct type and gauge in accordance with the equipment manufacturer's installation wiring requirements. I Switches for ancillary functions operate as per design and specification. Sipalay sile in the installed location. Sipalay sile in the installed location. I Displays are visible in the installed location. I Displays are visible in the installed location: I Displays are visible signal unit location: I Switche signal unit location: I Display at rouble signal unit of transponder is supervised. I Input wiring from control unit or transponder is supervised. I Input wiring from control unit or transponder is supervised. I Displays are visible signal unit location: I Display at rouble signal unit location: I Input wiring from control unit or transponder is supervised. I Input wiring from con		Individual alarm and supervisory zone indication operates.			
B and sequential display(s). Specify method of confirmation: Image: Specify method of confirmation: Minimum of one alarm zone and one supervisory zone tested per annunciator or sequential display to confirm operation. Image: Specify method of confirm operation. C Individual alarm and supervisory input zone designation labels are properly identified. Image: Specify method of confirm operation. C Individual alarm and supervisory input zone designation labels are properly identified. Image: Specify method of confirm operation. D Where active and supporting field devices are utilized, device labels correspond with actual field location. Image: Specify method of confirm operates. F Visual indicator test (lamp test) operates. Image: Specify method of confirm operates. Image: Specify method of confirm operates. Input wiring from control unit or transponder is supervised and of the correct type and gauge in accordance with the equipment manufacturer's installation wiring requirements. Image: Specify method of confirm operates. Image: Specify method of confirm operates. I Switches for ancillary functions operate as per design and specification. Image: Specify method of confirm operates. Image: Specify metho		the identical indication or lights the identical indicators at the other annunciator(s)			
Specify method of confirmation: Image: Specify method of confirmation: Minimum of one alarm zone and one supervisory zone tested per annunciator or sequential display to confirm operation. Image: Specify method of confirmation: C Individual alarm and supervisory input zone designation labels are properly identified. Image: Specify method of confirmation: D Where active and supporting field devices are utilized, device labels correspond with actual field location. Image: Specify method of confirmation: E Common trouble signal operates. Image: Specify method of the correct type and gauge in accordance with the equipment manufacturer's installation wiring requirements. Imput wiring from control unit or transponder is supervised and of the correct type and gauge in accordance with the equipment manufacturer's installation wiring requirements. Imput wiring from control unit or transponder is supervised and specification. Image: Specify method of confirmation operates. H Alarm signal silence visual indicator operates. Image: Specify method of confirmation operates. Image: Specify method of confirmation operates. Image: Specify method of confirmation of alarm signal and indication operates. Image: Specify method of confirmation operates. Image: Specify method operates. Image: Spe	В	and sequential display(s).			
Minimum of one alarm zone and one supervisory zone tested per annunciator or sequential display to confirm operation. Image: Confirm operation operation C Individual alarm and supervisory input zone designation labels are properly identified. Image: Confirm operation D Where active and supporting field devices are utilized, device labels correspond with actual field location. Image: Confirm operates E Common trouble signal operates. Image: Confirm operates Image: Confirm operates F Visual indicator test (lamp test) operates. Image: Confirm operates Image: Confirm operates Input wiring from control unit or transponder is supervised and of the correct type and gauge in accordance with the equipment manufacturer's installation wiring requirements. Image: Confirm operates Image: Confirm operates H Alarm signal silence visual indicator operates. Image: Confirm operates Image: Confirm operates Image: Confirm operates J Ancillary functions visual indicators operates. Image: Confirm operates Image: Confirm operates Image: Confirm operates L Displays are visible in the installed location. Image: Confirm operates Image: Confirm operates Image: Confirm operates L Displays are visible in the installed location: Image: Confirm operates Image: Confirm operates Image:		Specify method of confirmation:			
C Individual alarm and supervisory input zone designation labels are properly identified. Image: Construct the image		Minimum of one alarm zone and one supervisory zone tested per annunciator or sequential display to confirm operation.			
D Where active and supporting field devices are utilized, device labels correspond with actual field location. Image: Common trouble signal operates.	С	Individual alarm and supervisory input zone designation labels are properly identified.			
actual field location. Image: Common trouble signal operates. F Visual indicator test (lamp test) operates. Input wiring from control unit or transponder is supervised and of the correct type and gauge in accordance with the equipment manufacturer's installation wiring requirements. H Alarm signal silence visual indicator operates. I Switches for ancillary functions operate as per design and specification. J Ancillary functions visual indicators operates. K Manual activation of alarm signal and indication operates. L Displays are visible in the installed location. Yes No N/A Input wiring from control unit or transponder is supervised. B Visual indicators operates. C Ancillary functions visual indicators operates. L Displays are visible in the installed location. C 5.10 Remote Trouble Signal Unit Test And Inspection Yes No A input wiring from control unit or transponder is supervised. Yes No Audible trouble signal operates. C Audible trouble signal operates.	D	Where active and supporting field devices are utilized, device labels correspond with			
E Common trouble signal operates.	-	actual field location.			
F Visual indicator test (iamp test) operates. Imput wiring from control unit or transponder is supervised and of the correct type and gauge in accordance with the equipment manufacturer's installation wiring Imput wiring from control unit or transponder is supervised and of the correct type and gauge in accordance with the equipment manufacturer's installation wiring Imput wiring from control unit or transponder is supervised and of the correct type and gauge in accordance with the equipment manufacturer's installation wiring Imput wiring from control unit or transponder is supervised and specification. H Alarm signal silence visual indicator operates. Imput wiring from control unit or perates. Imput wiring from signal and indication operates. J Ancillary functions visual indicator operates. Imput wiring from control unit or transponder is supervised. Imput wiring from control unit or transponder is supervised. K Manual activation of alarm signal unit location: Imput wiring from control unit or transponder is supervised. Imput wiring from control unit or transponder is supervised. K Input wiring from control unit or transponder is supervised. Imput wiring from control unit or transponder is supervised. Imput wiring from control unit or transponder is supervised. B Visual trouble signal operates. Imput wiring from control unit or transponder is supervised. Imput wiring from control unit or transponder is supervised. Imput wiring from control unit or transponder is supervised. Imput wiring fr		Common trouble signal operates.	<u> </u>		<u> </u>
G gauge in accordance with the equipment manufacturer's installation wiring	F	Visual indicator test (lamp test) operates.			
H Alarm signal silence visual indicator operates. Image: Constraint of the installed location operates. I Switches for ancillary functions operate as per design and specification. Image: Constraint operates. J Ancillary functions visual indicators operates. Image: Constraint operates. K Manual activation of alarm signal and indication operates. Image: Constraint operates. L Displays are visible in the installed location. Image: Constraint operates. C C5.10 Remote Trouble Signal Unit Test And Inspection Remote trouble signal unit location: Image: Constraint operates. Remote trouble signal unit identification: Image: Constraint operates. A Input wiring from control unit or transponder is supervised. Image: Constraint operates. B Visual trouble signal operates. Image: Constraint operates. C Audible trouble signal operates. Image: Constraint operates. D Audible trouble signal silence operates. Image: Constraint operates.	G	gauge in accordance with the equipment manufacturer's installation wiring requirements.			
I Switches for ancillary functions operate as per design and specification. Image: Specification and the image is a specification operate is a specification. J Ancillary functions visual indicators operates. Image is a specification operate operate operate is a specification operate opera	Н	Alarm signal silence visual indicator operates.			
J Ancillary functions visual indicators operates. Image: Constraint of a larm signal and indication operates. Image: Constraint of a larm signal and indication operates. L Displays are visible in the installed location. Image: Constraint operates. Image: Constraint operates. C A linput wiring from control unit or transponder is supervised. Image: Constraint operates. Image: Constraint operates. C Audible trouble signal operates. Image: Constraint operates. Image: Constraint operates. D Audible trouble signal silence operates. Image: Constraint operates. Image: Constraint operates.	I	Switches for ancillary functions operate as per design and specification.			
K Manual activation of alarm signal and indication operates. Image: Constraint of alarm signal and indication operates. L Displays are visible in the installed location. Image: Constraint operates. C5.10 Remote Trouble Signal Unit Test And Inspection Remote trouble signal unit location: Remote trouble signal unit identification: Yes No N/A A Input wiring from control unit or transponder is supervised. Image: Constraint operates. B Visual trouble signal operates. Image: Constraint operates. C Audible trouble signal operates. Image: Constraint operates. D Audible trouble signal silence operates. Image: Constraint operates.	J	Ancillary functions visual indicators operates.			
L Displays are visible in the installed location. C5.10 Remote Trouble Signal Unit Test And Inspection Remote trouble signal unit location: Remote trouble signal unit location: Yes No N/A A Input wiring from control unit or transponder is supervised. Image: Colspan="2">Image: Colspan="2" Image: Colspan="2">Image: Colspan= 2" Image: Colspan="2	K	Manual activation of alarm signal and indication operates.			
C5.10 Remote Trouble Signal Unit Test And Inspection Remote trouble signal unit location: Yes No A Input wiring from control unit or transponder is supervised. Imput wiring from control unit or transponder is supervised. Imput wiring from control unit or transponder is supervised. Imput wiring from control unit or transponder is supervised. Imput wiring from control unit or transponder is supervised. Imput wiring from control unit or transponder is supervised. Imput wiring from control unit or transponder is supervised. Imput wiring from control unit or transponder is supervised. Imput wiring from control unit or transponder is supervised. Imput wiring from control unit or transponder is supervised. Imput wiring from control unit or transponder is supervised. Imput wiring from control unit or transponder is supervised. Imput wiring from control unit or transponder is supervised. Imput wiring from control unit or transponder is supervised. Imput wiring from control unit or transponder is supervised. Imput wiring from control unit or transponder is supervised. Imput wiring from control unit or transponder is supervised. Imput wiring from control unit or transponder is supervised. Imput wiring from control unit or transponder is supervised. Imput wiring from control unit or transponder is supervised. Imput wiring from control unit or transponder is supervised. Imput wiring from control unit or transponder is supervised. Imput wiring from control unit or transponder is supervised. Imput wiring from control unit or transponder is supervised.<	L	Displays are visible in the installed location.			
Remote trouble signal unit location: Yes No N/A A Input wiring from control unit or transponder is supervised. Image: Colspan="2">Image: Colspan="2" Image: Colspa="2" Image: Colspan="2" Image: Colspan="2" I		C5.10 Remote Trouble Signal Unit Test And Inspection			
Remote trouble signal unit identification: Yes No N/A A Input wiring from control unit or transponder is supervised. Image: Colspan="2">Image: Colspan="2" Image: Colspa="2" Image: Colspan="2" Image: Colspan="2" Image: Cols		Remote trouble signal unit location:			
Yes No N/A A Input wiring from control unit or transponder is supervised. Image: Control unit or transponder is supervised	R	emote trouble signal unit identification:			
A Input wiring from control unit or transponder is supervised. B Visual trouble signal operates. C Audible trouble signal operates. D Audible trouble signal silence operates.	^		Yes	No	N/A
C Audible trouble signal operates. D Audible trouble signal silence operates.	A	Input wring from control unit or transponder is supervised.			
D Audible trouble signal silence operates.	В	Visual trouble signal operates.			
	D	Audible trouble signal silence operates			

Date:		🗌 Au	ıdit	Verification
Building Name:	Address:			

C5.11 Printer Test				
	Printer Location: Printer Identification:			-
		Yes	No	N/A
А	Operates as per design and specification			
В	Zone of each alarm initiating device is correctly printed.			
С	Rated voltage is present.			

C5.12 Ancillary Device Circuit Test				
	Operation of			
	And	illary Ci	rcuit	
Depart Specific Type of Appillary Circuit	C	Confirme	d	
	Yes	NO	N/A	
	<u> </u>			
	<u> </u>	<u> </u>		
	<u> </u>			
	<u> </u>			
	<u> </u>	<u> </u>		
	<u> </u>	<u> </u>		

Note: The tests reported on this form do not include the actual operational test of ancillary devices except where noted.

Date: Building Name:

Address:

Verification

Audit

	C5.13 Interconnection to the Fire Signal Receiving Centre						
	Communicator Location:						
Circu	it Disconnect Means Location:						
Circu	it Panel/Breaker Identification:						
		Yes	No	N/A			
Α	The fire signal receiving centre transmitter is integral to the fire alarm control unit.						
В	The fire signal receiving centre transmitter is located remotely from the fire alarm control unit.						
С	Where an interconnection between the fire alarm control unit and a separate fire signal receiving centre transmitter is provided, a demarcation terminal box with a minimum of twelve (12) terminals is installed.						
D	The demarcation terminal box is located in the same room as the fire alarm control unit it is connected to.						
Е	The demarcation terminal box is labeled "Fire Alarm Demarcation" and/or "Limitation D'Alarme Incendie".						
F	The conductors installed between the fire alarm control panel and the demarcation terminal box complies with Section 3.4 of CAN/ULC-S524-06.						
G	Tested and confirmed operation of alarm relay.						
Н	Tested and confirmed operation of trouble relay.						
I	Tested and confirmed operation of supervisory relay.						
J	Confirm that the alarm transmission to the fire signal receiving centre is received.						
К	K Confirm that the supervisory transmission to the fire signal receiving centre is received.						
L	Confirm that the trouble transmission to the fire signal receiving centre is received.						
	Record the name and telephone number of the fire signal receiving centre.						
М	Address:						
N	Operation of the fire signal receiving centre transmitter bypass means results in a specific trouble indication at the fire alarm control unit or transponder and transmits a trouble signal to the fire signal receiving centre.						
Addit	ional Information (not mandated by the Standard):	Yes	No	N/A			
The co	mmunicator is installed in accordance with CAN/ULC-S561-13.						
The fire	e signal receiving centre is ULC Listed.						
The fire signal receiving centre ULC certification number is:							
The communicator is being tested in accordance with CAN/ULC-S561-13.							
Supporting documentation attesting to this is on site and has been reviewed.							
The U	The ULC "Central Station Fire Protective Signalling Service" Certificate is valid.						
The U	Lo Central Station Fire Protective Signalling Service" Certificate expires on:						
The las	The last inspection noted on the Certificate occurred on:						
I he communicator has been reset following completion of testing.							
The co	mmunicator nas been placed back into service.						

ADDITIONAL NOTES:

- 4. Smoke detector sensitivity measurement should be recorded in the "Remarks" column of the Individual Device Test Record. Analog smoke detectors may report their obscuration level (sensitivity) to the fire alarm's common control. This information should be retrieved and recorded in the "Remarks" column.
- 5. Status change, including time delay (where applicable), should be recorded in the "Remarks" column.
- Duct smoke detector pressure differential should be confirmed and recorded in the "Remarks" column. Detector tubes must be pulled and their alignment confirmed if results indicate any abnormalities. Record any discrepancies in the "Remarks" column.
- 7. Time delay setting of water flow switch should be recorded in the "Remarks" column.
- 8. Sprinkler supervisory switches should cause a "trouble" condition to be annunciated. This should be a latching type trouble (or "supervisory trouble") only restorable by pressing "Reset" on the fire alarm control panel. Exceptions must be noted in "Comments".
- 9. Upper and lower pressure setting of supervisory devices should be recorded in the "Remarks" column.
- 10. Low temperature setting should be recorded in the "Remarks" column.
- 11. Identify the specific ancillary devices in the "Remarks" column.
- 12. Where possible, identify the date a fire detector is changed. If housing discolouration is noted, attempt to identify the source and note the date of manufacture. Heat detectors whose labels are missing, faded and unreadable, or painted are considered failed and require replacement. This information should be noted in the "Remarks" column.
- 13. Identify type and function of each addressable device in the "Remarks" column.
- 14. Exposure to charging currents in excess of 100 mA will significantly shorten the service life of Ni-Cad and sealed lead acid batteries.
- Relays tied to listed fire alarm equipment initiating/supervisory circuits must be properly supervised. Note exceptions in "Comments".
 The system's documentation should provide information concerning the number of addressable devices that are connected to each isolator.
- Ensure this number does not exceed the Manufacturer's requirements. Any exceptions should be noted in "Comments".
- 17. The building owner/manager must maintain the records for the Verification on site for inspection by the local authority.
- 18. Operation of each annunciator or sequential display must be confirmed visually.
- 19. Stand-by batteries that are remotely located more than twelve (12) meters from the Fire Alarm Common Control must be fused (or installed in accordance with the manufacturer's recommendations or requirements).

Any exceptions to the above are noted in the "Remarks/Comments" area on the last page of this report.

Date:	
Building Name:	Address:

	C6.1 Field Device Testing - LEGEND					
Device	Description	Туре	Model Number			
	Manual Initiating Devices					
М	Manual pull station					
MAS	Manual Abort Station					
	Automatic Fire Detection Devices					
HD	Heat Detector, restorable or non-restorable, fixed temperature (12)					
RHD	Heat Detector, restorable, rate-of-rise thermostat (12)					
	Ionization Smoke detector (4)					
	Sensitivity Test Method (or Test Equipment Model/Method):					
S						
	Manufacturer's Sensitivity Test Range:					
	Photo-electric Smoke detector (4)					
	Sensitivity Test Method (or Test Equipment Model/Method):					
PS		-				
	Manufacturer's Sensitivity Test Range:					
	Dust Smalle datastan (4 5 0)					
	Duct Smoke detector (4, 5, 6)					
DC	Sensitivity rest method (or rest Equipment Model/Method):					
05	Manufacturar's Sansitivity Toot Banga	-				
	Manufacturer's Sensitivity rest Range.					
	Multi-Criteria type detector (specify detection types)					
	Sensitivity Test Method (or Test Equipment Model/Method):					
мс						
	Manufacturer's Sensitivity Test Range:					
CO	Carbon Monoxide detector					
OD	Other Detector type (specify)					
EOL(R)	End-of-Line resistor ("R" indicates "Power Supervision Relay")					
	Fire Sprinkler Devices					
FS	Sprinkler Flow Switch (7)					
FPS	Sprinkler Flow Pressure Switch (7)					
TS	Sprinkler valve supervisory Tamper Switch (8)					
LA	Low Air supervisory device (9)					
LT	Low Temperature supervisory device (10)					
HTC	Heat Trace Controller					
TLW	Tank Low Water supervisory device					
	Fire Alarm Signalling Devices					
В	Bell					
H	Horn					
BZ(5)	Mini Buzzer ("S" Indicates "silenceable" type)					
55B	Smoke Sounder Base					
V SP	Cone type Speaker					
	Horn Speaker					
۵V	Combination Audible/Visual Device - specify type (i.e. Horn/Strobe Unit)					
SCIM	Signal Circuit Isolation Module					
FT	Emergency Telephone (Fire Fighter's Phone)					
	Supporting Field Devices (Addressable Systems)					
RPM	Remote Point Module (13)					
SRIM	Single point Remote Initiating Module					
DRIM	Dual input Remote Initiating Module					
RPIM	Remote Point Isolator Module (16)					
SCRM	Signal Circuit Remote Module					
RRM(S)	Remote Relay Module ("S" provides supervised outputs)					
	Ancillary Devices					
DH(M,FL)	Door Holder ("M" is Magnetic, "FL" is Fusible Link)					
DM	Damper Motor					
R	Relay					
AD	Other Ancillary Device (11)					
SA	Smoke Alarm (specify single or multi-station type)					

Individual Device Record

Date:	
Building Name:	Address:
	L

Column Legend	
_	

A Correctly installed
 B Unit requires service, repair, missing, or cleaning
 C Alarm operation confirmed
 D Annunciator indication confirmed
 E Circuit number or address
 F Supervision and ground fault detection
 G Smoke detector sensitivity

"✓ "Yes - Acceptable "X" No – Unacceptable (Explain NO answers in comments) "Dash" - Not applicable

Location	Device	Α	В	С	D	E	F	G	Remarks
			<u> </u>		<u> </u>				
			<u> </u>		<u> </u>		<u> </u>		
L	l		I		I	I	I	l	1

Date:		
Building Name:	Address:	

C6.3 SIGNALLING DEVICE SOUND LEVEL MEASUREMENT

(Reference: Clause 5.10.1-C)

Zone	Location/Description	Ambient dBA	Alarm dBA	Remarks

Remarks/Comments

Date:	
Building Name:	Address:

C6.4 SIGNALLING DEVICE INTELLIGIBILITY MEASUREMENT

(Reference: CAN/ULC-S537-13 Clause 6.10.1-C and 6.10.1-G, OBC 2014 Sentence 3.2.4.22-2)

Zone	Location/Description	Intelligibility CIS	Remarks

Remarks/Comments

Date:	
Building Name:	Address:
C6 5 Defi	ziancios
CO.3 Den	

C6.6 Recommendations

Date:	
Building Name:	Address:
C6.7 Re	marks